

**BROKEN ARROW POST ACUTE HEALTH CARE
2450 N. STONE RIDGE DRIVE
INFRASTRUCTURE INVENTORY
BROKEN ARROW, OKLAHOMA**

Prepared By: sjb
Date: 10/9/14

Description	Units	Quantity	Unit Price	Extension
STORM				
ROW Clearing	LF	730.00	\$3.90	\$2,847.00
Excavation and Backfill	CY	1,020.00	\$23.60	\$24,072.00
Re-grade	LF	800.00	\$3.25	\$2,600.00
Manhole Tie-In's	EA	2.00	\$875.00	\$1,750.00
36" RCP Pipe	LF	216.00	\$42.00	\$9,072.00
42" HDPE Pipe	LF	520.00	\$51.00	\$26,520.00
72" ID Manhole	EA	1.00	\$2,420.00	\$2,420.00
96" ID Manhole	EA	3.00	\$2,740.00	\$8,220.00
Additional Depth	VF	1.00	\$140.00	\$140.00
Additional Depth	VF	7.00	\$200.00	\$1,400.00
Agg Base Material	TN	150.00	\$40.00	\$6,000.00
Shoring	EA	1.00	\$3,500.00	\$3,500.00
Total Cost of Storm Improvements =				\$88,541.00
Paving-Sidewalk				
Layout	EA	1.00	\$2,530.00	\$2,530.00
Sand	TN	340.00	\$21.00	\$7,140.00
5' Concrete Sidewalk	LF	3,700.00	\$11.20	\$41,440.00
Total Cost of Paving-Sidewalk Improvements =				\$51,110.00
Road Subgrade & Demolition				
Construction Entrance	EA	1.00	\$1,890.00	\$1,890.00
Erosion Control	LF	4,300.00	\$1.50	\$6,450.00
Strip Top Soil	SY	2,910.00	\$3.25	\$9,457.50
Subgrade	SY	2,910.00	\$5.66	\$16,470.60
Fly Ash	SY	2,110.00	\$8.08	\$17,048.80
Curb & Gutter	LF	1,420.00	\$18.65	\$26,483.00
Full Depth Saw Cut	LF	120.00	\$2.10	\$252.00
Remove Curb & Gutter	LF	120.00	\$11.20	\$1,344.00
Remove paving	SY	3,500.00	\$8.11	\$28,385.00
Remove Piping & Manholes	LF	1,005.00	\$12.60	\$12,663.00
Finish Grade	SY	3,111.00	\$3.10	\$9,644.10
Total Cost of Road Subgrade & Demolition Improvements =				\$130,088.00
Total Cost of Constructed Improvements =				\$269,739.00