

Time Manufacturing Co.
7601 Imperial Drive
Waco, Texas 76712-6608
254.399.2100



QUOTATION

SOURCEWELL N-25304R1

Customer: City of Broken Arrow
Attn: Ryan Baze
Email: RBaze@brokenarrowok.gov
Address: 485 North poplar Ave
Broken Arrow, OK 74012

Date: 8/8/2025
Model: VST-40-MHI

**VERSALIFT SOURCEWELL
CONTRACT #110421-TIM**

<u>Model</u>	<u>Description</u>	<u>Sourcewell Price</u>
VST-40-I	Insulated 40 ft. telescopic aerial platform lift, 45 ft. working height including the following standard feature items:	\$128,462.00

STANDARD SOURCEWELL FEATURES:

- 19,500 GVWR, 84" Ford F550 4X2 chassis with automatic transmission, 6.7L diesel engine, and air conditioning.
- 132" steel service body with standard compartments treadplate tops and 24" tailshelf.
- Standard platform capacity of 500 lbs. (204 kg).
- Standard 46-1/4" pedestal.
- Hydraulic pump.
- TruGuard™ 2.0 dielectric isolating system with Right Hand single stick control. All control handles are isolated and Tested per ANSI 92.2. The high resistive dielectric system is protected from direct environmental and job related contamination. TruGuard™ 2.0 technology incorporates the use of full hydraulic controls with durable metal handles and linkages
- Main A-frame outriggers.
- Full pressure turret mounted lower controls with override.
- Engine start/stop from platform and lower controls.
- Continuous rotation including one pass slip ring for start/stop system.
- Hydraulic 180 degree platform rotator.
- Six gpm (22.7 lpm) open center hydraulic system at 2500 psi (175 kg/cm²).
- Side mounted telescopic upper boom for low stowed platform.
- Fiberglass inner boom and patented ELECTROGARD provide insulation gap fully retracted meeting ANSI A92.2-2015 requirements for Category C, 46 KV and below.
- Chassis insulating system (fiberglass lower boom insert) providing 12 in. (0.30 m)
- Insulation gap and including accommodations to bridge insulation gap for testing per ANSI A92.2
- ELECTROGARD and inner boom furnished with white urethane paint over a white gel coat.
- Non-lube bearings used throughout.
- One set hydraulic tools at platform.
- Integral hydraulic oil reservoir with dual sight gauges and 17 gallon (64.4 l) capacity.
- Closed 24 in. X 24 in. X 42 in. (0.61m X 0.61m X 1.07m) fiberglass platform with one curbside step (in end hung position)
- Master/slave hydraulic leveling with upper control to tilt for cleanout or rescue.
- Upper boom storage cradle with ratchet type tie down strap and tubular rubber platform support
- PTO power source.
- 5lb Fire Extinguisher, reflector kit, and mudflaps
- Hydraulic oil.
- Mounting hardware.
- Two operator's manuals and two service manuals.
- ANSI A92.2 data plate.

CUSTOMER REQUESTED OPEN MARKET OPTIONS:

Open market items and options listed below in lieu of or in addition to above Sourcewell standard features and price _____ \$82,931.00

- VST47MHI insulated articulating telescopic aerial device in lieu of the above VST40I aerial device
- Hydraulic dual arm articulating jib pole and winch package for up to 1000lbs
- 24" x 30" x 42" closed platform with liner and cover in lieu of the above platform with liner and cover
- Emergency power
- Auto throttle.
- Full body safety harness and lanyard
- Install back-up alarm
- Wheel chocks and outrigger pads
- Install park brake interlock
- Combo pintle hitch with 2" ball, ICC bumper, D-rings and 7-prong trailer connector
- Two (2) amber strobe lights in grille and two (2) in tailshelf
- 132' long steel body with LED light package, master door locks, 30 long tailshelf, tailgates at side and rear, hotstick shelf with rear access door on streetside, side access at 2nd vertical on curbside, master door locks, undercoating, and wheel chock and outrigger pad storage in lieu of the above 132" steel service body
- 2025 Ford F550 4x4 cab and chassis with 84" CA and 19,500 lb. GVWR, 6.7 V* turbo diesel engine, 10 speed auto transmission, power windows and locks, engine block heater, trailer brake controller, high capacity trailer tow package, cruise control, keyless entry, AM/FM stereo with SYNC Communications System, and rear view camera in lieu of Sourcewell chassis above.
- 2000 watt inverter installed in front curbside compartment
- Cone holder installed on the streetside of the tailshelf

Price Summary

TOTAL PRICE F.O.B. WACO, TX.:	\$211,393.00
DELIVERY TO BROKEN ARROW, OK:	\$ 1,424.00
COMPLETE TOTAL PRICE F.O.B. MILLTOWN, NJ.	\$212,817.00

TERMS: Net 30 days. MSO to be sent after receipt of payment.

SHIPMENT: Approximately 90-120 days after receipt of order. This is a stock unit and is subject to prior sales.

NOTE: Price subject to change due to possible surcharges which will be added to the final total price.

Thank you for considering <VERSALIFT> to meet your utility equipment needs. We look forward to earning your business.

Sincerely,

Jeffrey Drews
Quote Manager
Phone: (254)420-5321
JeffreyDrews@versalift.com