



**Notes**

1. Erosion control fence will be installed before construction begins, and will be maintained until completion of the project.
2. Erosion control will be placed no closer than 11' from the center line of creek bed (closest point will be adjacent to South property line).
3. No fill, material, or structure will be placed East of erosion control barrier, i.e. nothing will be disturbed closer than 10' from the center line of the creek.
4. Water line to be run on the West side of erosion control barrier, in the west 7' of private utility easement.

