

LEGEND

SYMBOLS

- SIP • SET 3/8" IRON PIN
YELLOW CAP, STAMPED "CTA CA 973"
- FIP ○ FOUND IRON PIN
- MAG NAIL •
- POWER POLE •
- EXISTING SIGN ⚡
- EXISTING OIL WELL ☒
- TREE 🌳
- SS ○ SANITARY SEWER MANHOLE
- MH ○
- STORM SEWER PIPE ---
- GM ▲ GAS METER
- WV ⚡ WATER VALVE
- FH • FIRE HYDRANT ASSEMBLY
- WM • WATER METER
- L/E LANDSCAPE EASEMENT
- U/E UTILITY EASEMENT

LINEWORK

- RIGHT OF WAY LINE ———
- CURB AND GUTTER - - - - -
- EASEMENT - - - - -
- EDGE OF ASPHALT - - - - -
- EDGE OF GRAVEL - - - - -
- EDGE OF CONCRETE - - - - -
- SANITARY SEWER LINE SS --- SS
- GAS LINE G --- G
- WATER LINE W --- W
- FLOW LINE/DITCH ---
- POND/EDGE OF WATER - - - - -
- SECTION LINE - - - - -
- PROPERTY LINE - - - - -
- BARBWIRE X --- X
- CHAIN LINK FENCE ---
- CABLE FENCE X --- X
- PIPE FENCE ---
- LOT LINE ---
- TREE CANOPY LINE ---

BENCHMARK

BA 26
OKLAHOMA NORTH ZONE 3501
HORIZONTAL DATUM NAD 83 (1993)
NORTHING: 383229.887
EASTING: 2630291.884
VERTICAL DATUM NAVD 1988
ELEV. 670.307
DESCRIPTION OF BENCHMARK
5/8" REBAR - 1 1/2" ALUMINUM
CAP - FLUSH-STAMPED "BA26", SET
S.E. OF 91ST ST. AND 193RD E. AVE..

FLOODPLAIN REFERENCE

FIRM PANEL NO. 40143CO392KL DATED AUGUST 3, 2009 CLASSIFIES THE PROPERTY DESCRIBED HEREON AS ZONE "X", AN AREA DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN.

THE ABOVE STATEMENT IS FOR INFORMATION ONLY AND THIS SURVEYOR ASSUMES NO LIABILITY FOR THE CORRECTNESS OF THE CITED MAP(S). IN ADDITION, THE ABOVE STATEMENT DOES NOT REPRESENT THIS SURVEYOR'S OPINION OF THE PROBABILITY OF FLOODING.

BASIS OF BEARING



THE WEST LINE OF SW/4
S 01°17'35" E

SITE INFORMATION:	
ADDRESS	91st ST S & LYNN LANE
ZONING	RS-3
LOTS	244
BLOCKS	17
AREA	87.277 ACRES
WATER SUPPLY	CITY OF BROKEN ARROW
MINIMUM LOT SF (EA)	7000
FRONT BUILDING SETBACK	25 FT
REAR BUILDING SETBACK	20 FT
SIDE SETBACKS	5 FT
FRONT LOT UTILITY ESMT	15 FT
REAR LOT UTILITY ESMT	11 FT
PROPERTY PERIMETER ESMT	17.5 FT
RESERVE AREA	4.98 ACRES

PROPERTY DESCRIPTION

A TRACT OF LAND BEING A PART OF THE SOUTH HALF (S/2) OF THE SOUTHWEST QUARTER (SW/4) OF SECTION THIRTEEN (13), TOWNSHIP EIGHTEEN (18) NORTH, RANGE FOURTEEN (14) EAST, TULSA COUNTY, OKLAHOMA BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS, TO-WIT;

COMMENCING AT THE SOUTHWEST CORNER OF THE SOUTHWEST QUARTER (SW/4), THENCE N 88°45'07" E ALONG THE SOUTH LINE OF SAID SOUTHWEST QUARTER (SW/4) A DISTANCE OF 1406.93 FEET TO THE POINT OF BEGINNING; THENCE N 01°18'21" W A DISTANCE OF 741.94 FEET; THENCE S 88°45'45" W A DISTANCE OF 642.34 FEET; THENCE N 01°15'55" W A DISTANCE OF 249.52 FEET; THENCE S 88°45'28" W A DISTANCE OF 764.55 FEET TO THE WEST LINE OF SAID SOUTHWEST QUARTER (SW/4); THENCE N 01°17'35" W ALONG THE SAID WEST LINE A DISTANCE OF 991.65 FEET TO THE NORTHWEST CORNER OF THE SOUTH HALF OF THE NORTH HALF OF THE SOUTHWEST QUARTER (S/2 N/2 SW/4); THENCE N 88°46'13" E ALONG THE NORTH LINE OF SAID SOUTH HALF NORTH HALF SOUTHWEST QUARTER (S/2 N/2 SW/4) A DISTANCE OF 1960.56 FEET; THENCE S 01°18'34" E A DISTANCE OF 316.20 FEET; THENCE N 88°46'13" E A DISTANCE OF 689.03 FEET TO A POINT ON THE EAST LINE OF SAID SOUTHWEST QUARTER (SW/4); THENCE S 01°18'34" E ALONG SAID EAST LINE A DISTANCE OF 1666.26 FEET TO THE SOUTHEAST CORNER OF THE SOUTHWEST QUARTER (SW/4); THENCE S 88°45'07" W ALONG THE SOUTH LINE OF SAID SOUTHWEST QUARTER (SW/4) A DISTANCE OF 1243.22 FEET TO THE POINT OF BEGINNING, CONTAINING 87.277 ACRES, MORE OR LESS. SAID TRACT OF LAND IS SUBJECT TO ANY AND ALL RIGHT-OF-WAYS OF RECORD.



CURRENT OWNER:
DON & MARY COUCH
56 LAKEVIEW CIRCLE
LAWTON, OK 73507
PH 580.695.1825


ENGINEER/SURVEYOR:
CRAFTON TULL
220 E. 8TH ST.
TULSA, OK 74119
PH 918.584.0347

220 E. 8th Street
Tulsa, Oklahoma 74119

Crafton Tull
architecture | engineering | surveying

918.584.0347 | 918.584.3783 | www.craftontull.com

CERTIFICATE OF AUTHORIZATION
CA 973 (PE/LS) EXPIRES 6/30/2018




CROSSINGS AT LYNN LANE
E. 9th St. S. (S. LYNN LANE RD.) &
WASHINGTON ST. (E. 91st ST.)
BROKEN ARROW, OKLAHOMA

Key Plan

No.	Description	Date

This document, and the ideas and designs incorporated herein, as an instrument of professional service, is the property of Crafton, Tull & Associates, Inc., and is not to be used, in whole or in part, for any other project, without the written authorization of Crafton, Tull & Associates, Inc.

PROJECT NO: 15108900
ISSUE DATE: 07/18/2016
CONTACT: B. WATSON
CHECKED BY:



© 2016 Crafton, Tull & Associates, Inc.

PRELIMINARY PLAT - 1 OF 5

DRAWING: G:\DRAWING\2016\15108900\20160718\DD-42116-06.DWG (PRELIMINARY PLAT) PLOTTED: 07/18/2016 10:00 AM. PLOTTED BY: A. B. WATSON JR. (LS 1057) CRAFTON TULL & ASSOCIATES, INC.