

DATE	REVISIONS	DESIGN	DRAWN	DATE
		DOS	DOS	12/2022
		REVIEWED	PROJECT NO.	
		APPROVED	SHEET	
		OF		



# UTILITY REVENUE FUNDING PROJECT REINVESTING IN OUR FUTURE

**PROJECT NAME**  
**FUNDING SOURCE**

CONTRACTOR:

NAME OF CONTRACTOR

ARCHITECT / ENGINEER:

NAME OF DESIGN FIRM

GENERAL MANAGER: MICHAEL SPURGEON

BROKEN ARROW COUNCIL


CHAIRPERSON: DEBRA WIMPEE, WARD ONE

VICE-CHAIRPERSON: JONNIE PARKS, AT LARGE

TRUSTEE: LISA FORD, WARD TWO

TRUSTEE: JUSTIN GREEN, WARD FOUR

TRUSTEE: DAVID PICKEL, WARD THREE



## NOTES:

SIGN TO BE CONSTRUCTED FROM 1/2" PLYWOOD (EXTERIOR).  
FONT: AERIAL BOLD, HELVETICA BOLD, OR EQUAL.  
BOLTS: 5/16" DIA. GR. 5 FLANGED GALVANIZED BOLT WITH 2 FLAT WASHERS AND GR. 5 SERRATED FLANGED NUT (12 REQUIRED).  
CITY LOGO TO BE PROVIDED BY THE CITY OF BROKEN ARROW.  
PROJECT NAME WILL NOT EXCEED 2 LINES.  
POST TUBES SHALL MEET ASTM A1011 GRADE 50.  
POST TUBE GALVANIZED AS PER ASTM A653 GRADE 90.

7. HEAVY DUTY ANCHOR TUBE SHALL MEET A500 GRADE B. STRUCTURAL TUBE AND STEEL SHALL BE HOT DIP GALVANIZED PER ASTM A123.  
8. THE UPPER SIGN POST SHALL TELESCOPE INSIDE THE ANCHOR TUBE. A MINIMUM OF 12" ANCHOR TUBE SHALL BE A MINIMUM OF 30" WITH 3" MAXIMUM PROJECTION.  
9. THE CONCRETE FOOTING SHALL BE CLASS "A" CONCRETE.  
10. PRICE BID FOR PROJECT SIGN SHALL INCLUDE ALL MATERIALS, EQUIPMENT, LABOR AND INCIDENTALS REQUIRED FOR EACH IN-PLACE COMPLETE PROJECT SIGN.

11. COMPLETE PROJECT SIGN REMOVAL AT COMPLETION OF PROJECT.  
12. PROGRESS AND PERCENT COMPLETE UPDATE TO BE BY CONTRACTOR AS DIRECTED BY ENGINEER.  
13. THE USE OF THE CITY LOGO MUST CONFORM TO THESE STANDARDS. FOR SUN USE RGB: R:250 G:155 B:52. FOR ARROW, BOW AND LETTERING USE RGB: R:19 G:61 B:141. LETTERING FONT SHALL BE "PAPYRUS"