

MPH

CONSTRUCTION 1

Mike Hammons 918.706.2375

General Contractor

107 W Commercial

Office of Russell Peterson Attorney

Basic Scope of work for Exterior

- Remove existing metal canopy and wood exterior
- Remove old wood windows
- Fur-out existing wall with 2-1/2 18 gauge studs and 1/2 inch Densglass sheathing
- Tyvek Weather barrier over sheathing
- Install Chosen "Old Myford" thin brick across entire office Front
- Brick to extend from Sidewalk up to top of Parapet Wall
- Install new Parapet wall cap similar to Main Street Taverns
- Install new Black Canvas type awnings to coordinate with surrounding businesses
- Install new Commercial windows to coordinate with surrounding businesses
- Install stone type Sills to coordinate with surrounding businesses

